



ABBNEY PYNFORD



## FLOODSAFE

### Far Away\_ Surrey

**Value:** £60,000

**Size:** 135m<sup>2</sup>

**Duration:** 6 weeks

**Rig:** Klemm 709

#### Scope of work:

- ▶ Suspended raft designed in-house
- ▶ Setting out of foundation works
- ▶ On site supervision of works (Working foreman & visiting Engineer)
- ▶ 50mm concrete working surface acting as a stable, weatherproof base for the formwork
- ▶ 300mm Dia CFA piles not exceeding 10.5m in length to our design (F.O.S = 3.0)
- ▶ 300x300mm Columns to Support Structural Slab
- ▶ 1No. Voided Housedeck structural slab (135m<sup>2</sup>)
- ▶ 1.2m void to underside of Housedeck slab to accommodate flood risk
- ▶ Straight edge detail with 15mm chamfer at the top and bottom of the suspended slab
- ▶ Under slab drainage and services



**Get in touch to discuss your project requirements:**

**e:** [info@abbeypynford.co.uk](mailto:info@abbeypynford.co.uk)

**t:** 01442 212112

[abbeypynford.co.uk](http://abbeypynford.co.uk)

